CITY
ENGINEER

2101 O'Neil Avenue
Cheyenne, WY 82001
(307) 637-6268
cheyennecity.org

MEMORANDUM

DATE: October 26, 2026

TO: Honorable Mayor Patrick J. Collins
Mark Francisco, Chief of Police
Thomas Cobb, PE, City Engineer

FROM: Rick Amen, PE, City Traffic Engineer



Agenda items Critical Traffic Control Committee
October 26, 2026, 11:00 a.m.

SUBJECT: **Report and Recommendation Critical Corridor Petitions**

I. Petitions Under Review

26-4 W. 8th Avenue (Speeding & Safety)
Status: Open since 10/6/26; avg speeds between 29- 35 MPH and 95 percentile speed of 37 MPH. Interim treatment recommended to install radar feedback signs until the traffic signal and pedestrian crosswalk treatments can be designed and installed at 8th & Carey (signal) and 8th & Pioneer (crosswalk with RRFB). Curb extensions will be included at both locations to improve safety.

Next Steps: Recommend not to proceed with designation as a critical corridor but to include improvement of operations with a future 8th Avenue project intended to be constructed in the summer of 2027.

II. Next Meeting Date: November 23, 2026; 11:00 a.m.