City of Cheyenne - Purchasing
2101 O'Neil Avenue, Room 309
Cheyenne, WY 82001
307-773-1045
tbarttelbort@cheyennecity.org

ADDENDUM NUMBER THREE
BID S-1-21

To: All Prospective Bidders and all others concerned

From: City of Cheyenne, Purchasing Manager, TJ Barttelbort

Date: January 19, 2021

Subject: Addendum Number Three to Bid S-1-21 for the 24th Street Mill and Overlay Project

---

The changes, clarifications, omissions, additions, and/or alterations in, on, and to the bid information and specifications shall apply to the Invitation For Bid submitted for and to the project indicated above. Except as modified by this Addendum Number Three, all of the terms and provisions of the Invitation for Bid for the above listed project remain in full force and effect. This Addendum Number Three supersedes all previous instructions pertaining to the items listed:

Clarification

C1: A revised Itemized Bid Sheet is included with this Addendum Three. Bidders shall use the revised Itemized Bid Sheet provided with this Addendum for their Bid submission.

C2: Line Item 02895 is updated from Alternate #1 Deduct, to ALTERNATE #1 IN LIEU OF LINE ITEM 04001. Bidders shall provide a Price for the MIRIFI PGM-G100-100 PAVING GRID on Line Item 04001, and shall provide a price for PAVING FABRIC on Line Item 02895. The City will award only one (1) of these line items, based on funding availability.

ADDENDUM THREE ACKNOWLEDGED:

BY_____ TITLE_____
(Addendum **must** be signed and returned with bid or receipt of the addendum **must** be acknowledged on the Invitation to Bid).

REMAINDER OF PAGE INTENTIONALLY LEFT BLANK

ADDENDUM THREE PROJECT: 24TH STREET MILL & OVERLAY				BID NO. S-1-21	BID TAB
ITEM NO.	**DESCRIPTION**	**UNIT**	**QUANTITY**	**UNIT PRICE**	**TOTAL COST**
01000	PERFORMANCE BOND	BOND	1		
01000	MOBILIZATION	LS	1		
01000	FORCE ACCOUNT	FA	1	60,000.00	$ 60,000.00
01000	BNSF RAILROAD PERMIT	LS	1		
01000	BNSF RAILROAD FLAGGING	DAYS	6	1,500.00	$ 9,000.00
01050.01	TRAFFIC CONTROL, INCLUDES TWO MESSAGE BOARDS TO BE USED AT THE CITY'S DISCRETION.	LS	1		
1050.02	FLAGGING	HR	450		
1050.03	SPECIALTY SIGNS	SQFT	20		
01563	SEDIMENT EROSION CONTROL AND STORM WATER MANAGEMENT	LS	1		
02076.01	COLD ASPHALT MILLING, FULL WIDTH, @ 1 -1/2"	SQ YD	11,368		
02076.02	CONCRETE MILLING, FULL WIDTH, @ 2 -1/4"	SQ YD	10,590		
02210	UNCLASSIFIED EXCAVATION, INCLUDES COMPACTED GRADING "W" BASE	CU YD	500		
02280	TOPSOIL, 6" DEEP	SQ YD	262		
02512.01	BITUMINOUS PAVING GRADING 1/2" 70-28 OIL, GRANITE AGGREGATE	TON	2,625		
02512.02	LEVELING COURSE, 3/4" LIFT, 3/8" AGGREGATE, 64-28 OIL	TON	477		

02515.01	R&R BITUMINOUS PATCH, 6" ASPHALT, GRANITE AGGREGATE, OVER 6" COMPACTED GRADING "W"	SQ YD	870		
02515.02	ADDITIONAL "AFTER MILLING"PATCHING BITUMINOUS PATCH, 6" ASPHALT, GRANITE	SQ YD	766		
02570.01	ADJUST WATER OR GAS VALVE, INCLUDES NEW TOP SECTION, LID AND CONCRETE COLLAR	EA	14		
02570.02	ADJUST MANHOLE, INCLUDES NEW RING, LID AND CONCRETE COLLAR	EA	13		
02725	R&R TYPE "A" INLET, COMPLETE IN PLACE	EA	5		
02805.01	R&R EXISTING SIGN	EA	4		
02805.02	NEW SIGN POST, INCLUDES NEW HARDWARE	LN FT	24		
02900.01	LAWN SEED	SQ YD	262		
02900.02	SPRINKLER HEAD, MATCH EXISTING	EA	20		
02900.03	1/2" PE PIPE, "SWING " OR "FUNNY"	LN FT	75		
03330.01	R&R TYPE "A" CURB AND GUTTER , 24", INCLUDES 6" COMPACTED GRADING "W" BASE	LN FT	4,437		
03330.02	TYPE "C" LANDSCAPE CURB	LN FT	250		
03340.01	R&R SIDEWALK 4", INCLUDES 4" COMPACTED GRADING "W" BASE	SQFT	6,360		
03340.02	R&R RESIDENTIAL DRIVE APPROACH 6", INCLUDES 6" COMPACTED GRADING "W" BASE	SQFT	230		
03340.03	R&R COMMERCIAL DRIVE APPROACH 8", INCLUDES 6" COMPACTED GRADING "W" BASE	SQFT	2,655		
03340.04	DETECTABLE WARNING PLATES, 24" X 24" EAST JORDAN #700571 OR NEENAH # 4984-24Q	EA	55		
03340.05	R&R VALLEY PAN 8", INCLUDES 6" COMPACTED GRADING "W" BASE	SQFT	480		

03340.06	R&R FILLET 8", INCLUDES 6" COMPACTED GRADING"W" BASE	SQFT	1,395		
04001	MIRIFI PGM-G100-100 PAVING GRID	SQ YD	10,590		
04002.01	THERMOPLASTIC CROSSWALK BARS 18" X 9'. PREMARK NO. 8431067 NON-CONTRAST OR EQUAL	SQ FT	864		
04002.02	THERMOPLASTIC CROSSWALK BARS 24" X 9'. PREMARK NO. 8431067 CONTRAST OR EQUAL	SQ FT	252		
04002.02	THERMOPLASTIC STOP BAR 2' WIDE, PREMARK NO. 8430566 OR EQUAL	SQ FT	576		
04002.03	THERMOPLASTIC "RAILROAD CROSSING" SYMBOL, PREMARK NO. PMK 8130103A OR EQUAL	EA	4		
04002.04	THERMOPLASTIC "LEFT TURN ARROW" , PREMARK NO. 8330241L OR EQUAL	EA	2		
04003	COLORED, STAMPED CONCRETE, 4" INCLUDEDS 4" COMPACTED GRADING 'W' BASE	SQ FT	126		
				TOTAL BID	

ALTERNATE #1 IN LIEU OF LINE ITEM 04001

02895	PAVING FABRIC. LINE ITEM TO BE USED IN LIEU OF MIRAFI PGM-G100-100 PAVING GRID	SQ YD	10,590		

COMPANY NAME:

ADDRESS:

CITY, STATE, ZIP:

BIDDER'S SIGNATURE: