



City of Cheyenne - Purchasing
2101 O'Neil Avenue, Room 309
Cheyenne, WY 82001
307-773-1045
tbarttelbort@cheyennecity.org

ADDENDUM NUMBER TWO

BID S-3-22

To: All Prospective Bidders and all others concerned

From: City of Cheyenne, Purchasing Manager, TJ Barttelbort

Date: September 3, 2021

Subject: **Addendum Number Two to Bid S-3-22 for the Carey Avenue Multi Use Path Project**

The changes, clarifications, omissions, additions, and/or alterations in, on, and to the bid information and specifications shall apply to the Invitation For Bid submitted for and to the project indicated above. Except as modified by this Addendum Number Two, all of the terms and provisions of the Invitation for Bid for the above listed project remain in full force and effect. This Addendum Number Two supersedes all previous instructions pertaining to the items listed:

BID DUE DATE REVISION:

The Governing Body of the City of Cheyenne, Wyoming ("the Governing Body") will receive sealed bid proposals at the Office of the City Purchasing Agent, located in Room 309 of the Municipal Building at 2101 O'Neil Avenue, Cheyenne, WY 82001, until 2:00 p.m. local time on the **14th day of September, 2021**, ~~9th day of September, 2021~~, for the "**Carey Avenue Multi Use Path**" project.


REVISION:

R1: The quantity of Type "A" Curb and Gutter for the Road Project has been increased to 285 LF. This brings the total quantity of Type "A" Curb and Gutter to 590 LF. This revision has been shown within the summary on Sheet S3. Bid Item 3340.7 has been revised to reflect this quantity increase. Bidders shall use the included, updated bid tab for their bid submittal (Provided in PDF & Excel Formats).

ADDENDUM TWO ACKNOWLEDGED:

BY _____ TITLE _____

(Addendum **must** be signed and returned with bid or receipt of the addendum **must** be acknowledged on the Invitation to Bid).

	<u>CITY OF CHEYENNE ITEMIZED BID SHEET FORM</u>
BID SHEET, BASE BID	
BID PROPOSAL	
PROJECT	CAREY AVENUE MULTI USE PATH

Item No.	Description	Unit	Est. Quantity		Total	Unity Price (in figures)	Total Price
			Path Proj.	Road Proj.	Est. Quantity		
1000.1	CONTRACT BOND	LS	0.93	0.07	1		
1020.1	INSPECTIONS AND TESTING FOR QUALITY CONTROL	LS	0.93	0.07	1		
1030.1	MOBILIZATION	LS	0.93	0.07	1		
1035.1	MISCELLANEOUS FORCE ACCOUNT	\$	23,000	2,000	\$25,000	\$1.00	\$25,000.00
1050.1	TRAFFIC CONTROL	LS	0.50	0.50	1		
1563.1	SEDIMENT, EROSION CONTROL, AND STORM WATER MANAGEMENT	LS	0.93	0.07	1		
2075.1	REMOVAL OF CONCRETE SIDEWALK, INCL. SAW CUT	SY	230		230		
2075.2	REMOVAL OF ASPHALT SIDEWALK, INCL. SAW CUT	SY	280		280		
2075.3	REMOVAL OF ASPHALT PAVEMENT, INCL. SAW CUT	SY	42	200	242		
2075.4	REMOVAL OF CURB & GUTTER	LF	220		220		
2075.5	REMOVAL OF VALLEY PAN AND FILLETS	SY	90		90		
2076.1	COLD MILLING EXISTING ASPHALT (3/4")	SY	370		370		
2110.1	CLEARING AND GRUBBING OF SHRUBS	LS	1		1		
2110.2	REMOVE TREE (18" DIA)	EA	4		4		
2110.3	REMOVE TREE (24" DIA)	EA	2		2		
2110.4	REMOVE TREE (48" DIA)	EA	1		1		
2110.5	CLEANING VALLEY PAN/DRAIN PAN/PIPE AT CFD MUSEUM PARKING LOT	LS		1	1		

Item No.	Description	Unit	Est. Quantity		Total	Unity Price (in figures)	Total Price
			Path Proj.	Road Proj.	Est. Quantity		
2210.1	UNCLASSIFIED EXCAVATION	CY	700	20	720		
2231.1	CRUSHED BASE GRADING 'W'	TON	1,425	38	1,463		
2280.1	TOPSOIL STORING, STRIPPING, PLACING (4")	CY	740		740		
2512.1	PLANT MIX BITUMINOUS PAVEMENT (1.5" LIFT)	SY	370		370		
2515.1	PATCHING ASPHALT (INCL. SAW CUT, REMOVAL, CRUSHED BASE, ASPHALT)	SF	1,250	640	1,890		
2725.1	FRENCH DRAIN	LF		22	22		
2805.1	RELOCATE/RESET EXISTING SIGN (COMPLETE INSTALLATION)	EA	5		5		
2805.2	SIGN PANEL	SF	4		4		
2895.1	ENGINEERING FABRIC	SY	84		84		
2900.1	SEEDING, DRY LAND MIX	SY	1,305		1,305		
2900.2	SOD	SY	1,725		1,725		
2900.3	SKYLINE HONEYLOCUST TREE	EA	2		2		
2900.4	HACKBERRY TREE	EA	2		2		
2900.5	SENTRY AMERICAN LINDEN TREE	EA	3		3		
2900.6	ACCOLADE ELM TREE	EA	2		2		
2900.7	CARDINAL ROYAL MT. ASH TREE	EA	3		3		
2900.8	WEED BARRIER FABRIC	SY		60	60		
2900.9	ROCK MULCH	CF		330	330		
2900.10	3" CLASS 200 PVC MAINLINE	LF	200		200		
2900.11	RELOCATE VALVE	EA	2		2		
2900.12	ADJUST HEADS/ EXTEND LATERALS	LS	1		1		

Item No.	Description	Unit	Est. Quantity		Total	Unity Price (in figures)	Total Price
			Path Proj.	Road Proj.	Est. Quantity		
2900.13	REMOVE SPRAY ZONE, INCL. CAP	LS	1		1		
2900.14	SLEEVE UNDER NEW PATH	EA	3		3		
2900.15	RELOCATE LATERAL	LF	40		40		
3340.1	CONCRETE GREENWAY, 8"	SF	990		990		
3340.2	CONCRETE GREENWAY, 4"	SF	43,400		43,400		
3340.3	RED COLORED CONCRETE, 4"	SF	635		635		
3340.4	DETECTABLE WARNING PLATES (2'x2' PLATES)	EA	3		3		
3340.5	DETECTABLE WARNING PLATES (2'x2.5' PLATES)	EA	14		14		
3340.6	DETECTABLE WARNING PLATES (2' WIDE ON A 20' RADIUS)	LF	45		45		
3340.7	CURB AND GUTTER, TYPE A	LF	305	285	590		
3340.8	CURB AND GUTTER, TYPE B	LF	180		180		
3340.9	CURB TURN FILLETS (3' RADIUS)	EA		4	4		
3340.11	CURB TURN FILLETS (20' RADIUS)	EA	4		4		
3340.12	CONCRETE VALLEY PAN, 8"	SY	37		37		
3340.13	CONCRETE APPROACH, 8"	SY	57	75	132		
3340.14	3' DRAIN PAN	EA		4	4		
4000.0	THERMOPLASTIC CROSSWALK	SF	108		108		
4000.1	THERMOPLASTIC STOP BAR	SF	60		60		
4005.1	CFD MUSEUM FENCE	LF		110	110		
4010.1	TRIM TREES AND SHRUBS FOR CLEARANCE	LS	1		1		

COMPANY NAME: _____

TOTAL: _____

REMOVAL OF CONCRETE SIDEWALK, CURB & GUTTER, FILLETS & VALLEY PANS (PATH PROJ.)

STATION TO STATION	SY	SY	SY	LF	SY
	REMOVAL OF CONCRETE SIDEWALK, INCL. SAW CUT	REMOVAL OF ASPHALT SIDEWALK, INCL. SAW CUT	REMOVAL OF ASPHALT PAVEMENT, INCL. SAW CUT	REMOVAL OF CURB & GUTTER	REMOVAL OF VALLEY PANS AND FILLETS
20+55 - 21+70	25			105	42
28+50 - 31+33	186			40	
34+40 - 35+15				64	24
39+40 - 40+56		129			
BUS STOP			40		19
PARKING LOT CONNECTOR	4	133			
TOTAL	215	262	40	209	85
FOR ESTIMATE	230	280	42	220	90

ASPHALT & CONCRETE REMOVALS AND PATCHING (ROAD PROJ./ BID ALTERNATE)

LOCATION	SY	SF
	REMOVAL OF ASPHALT PAVEMENT, INCL. SAW CUT	PATCHING ASPHALT
CFD PARKING AREA	190	611
TOTAL	190	611
FOR ESTIMATE	200	640

PATCHING ASPHALT (PATH PROJ.)

STATION TO STATION	SF
7+70	20
14+24.50 - 14+56.50	64
18+15.00 - 18+50.00	72
20+55.40 - 21+31.20	295
29+33.80 - 29+83.00	80
34+39.50 - 34+63.00	44
34+99.50 - 35+13.25	44
BUS STOP	573
TOTAL	1,192
FOR ESTIMATE	1,250

NOTE: THE PATCHING ASPHALT BID ITEM ALSO INCLUDES: SAW CUT, REMOVAL, CRUSHED BASE, AND ASPHALT.

CONCRETE SIDEWALK, CURB & GUTTER, FILLETS & VALLEY PANS (PATH PROJECT)

STATION TO STATION	SF	SF	SF	SY	LF	LF	EA	SY	SY	TON
	CONCRETE GREENWAY, 4"	CONCRETE GREENWAY, 8"	RED COLORED CONCRETE, 4"	ENGINEERING FABRIC	CURB & GUTTER TYPE A	CURB & GUTTER TYPE B	CURB TURN FILLET (20' RADIUS)	CONCRETE APPROACH, 8"	CONCRETE VALLEY PAN, 8"	CRUSHED BASE
0+00 - 8+00	7,396			80	10					247
8+00 - 21+00	12,301	941	167		101		1		35	418
21+00 - 34+80	14,069		436		146		2			428
34+80 - 40+56	5,566				32		1			173
PARKING LOT CONNECTOR	1,213									38
BUS STOP	869					172		54		53
TOTAL	41,414	941	603	80	289	172	4	54	35	1,357
FOR ESTIMATE	43,400	990	635	84	305	180	4	57	37	1,425

CONCRETE SIDEWALK, CURB & GUTTER, FILLETS & VALLEY PANS (ROAD PROJECT/BID ALTERNATE)

LOCATION	SY	LF	EA	EA	TON
	CONCRETE APPROACH, 8"	CURB & GUTTER TYPE A	3' DRAIN PAN	CURB TURN FILLET (3' RADIUS)	CRUSHED BASE
CFD PARKING AREA	70	271	4	4	46
TOTAL	70	271	4	4	46
FOR ESTIMATE	75	285	4	4	49

ADDENDUM #2

FRENCH DRAIN (ROAD PROJECT / BID ALTERNATE)

FRENCH DRAIN SHALL INCLUDE THE COMPLETE INSTALLATION OF:

- EXCAVATION FOR DRAIN SYSTEM
- 4" PERF PIPE, WRAPPED IN FILTER FABRIC
- 3/8" CRUSHED GRANITE MATERIAL (WASHED)
- FILTER FABRIC AROUND TRENCH SIDES AND BOTTOM
- GRANITE BOULDERS, 1' MIN. ON SHORTEST SIDE
- RESTORING EXISTING SITE CONDITIONS ADJACENT TO FRENCH DRAIN

CFD MUSEUM FENCE (ROAD PROJECT / BID ALTERNATE)

FENCE SHALL INCLUDE THE COMPLETE INSTALLATION OF:

- SEVEN (7) PILLARS, 2'x2', MATCH EXISTING STYLE AND COLOR
- DOWELED PRESSURE TREATED 3 RAIL FENCE, MATCH EXISTING IN STYLE AND COLOR
- SIX (6) LINE POSTS

ASPHALT MILLING & WEARING COURSE (PATH PROJECT)

LOCATION	SY	SY
	COLD MILLING ASPHALT PAVEMENT (3/4")	PLANT MIX BITUMINOUS PAVEMENT (1.5" LIFT)
LIONS PARK DR & CAREY AVE.	350	350
TOTAL	350	350
FOR ESTIMATE	370	370

PLANT MIX SHALL HAVE 1/2" MAX AGGREGATE TYPE II.

SUMMIT ENGINEERING, LLC

5907 TOWNSEND PLACE
CHEYENNE, WY. 82009
307-637-0681



DESIGNED: DMH
DRAWN: DMH
CHECKED: LRG
PROJECT MANAGER: DMH
DATE: MAY 2021

CAREY AVE. MULTI USE PATH

SUMMARIES

DRAWING

S3 OF S4