



City of Cheyenne - Purchasing  
2101 O'Neil Avenue, Room 309  
Cheyenne, WY 82001  
307-773-1045  
tbarttelbort@cheyennecity.org

## ADDENDUM NUMBER ONE BID S-9-23

To: All Prospective Bidders and all others concerned

From: City of Cheyenne, Purchasing Manager, TJ Barttelbort

Date: January 10, 2023

**Subject: Addendum Number One to Bid S-9-23 for Sanitation Division Transfer Station Welding Repairs**

---

The changes, clarifications, omissions, additions, and/or alterations in, on, and to the bid information and specifications shall apply to the Invitation For Bid submitted for and to the project indicated above. Except as modified by this Addendum Number One, all of the terms and provisions of the Invitation for Bid for the above listed project remain in full force and effect. This Addendum Number One supersedes all previous instructions pertaining to the items listed:

### REVISED ITEMIZED BID SHEET:

A revised Itemized Bid Sheet is included with this Addendum for use by bidders. The revised Bid Sheet changes the Estimated Quantity for the Dumping Pit Repairs from Linear Foot, to Lump Sum.

Additional funding has been added to the force account as well.

### PROJECT COMPLETION:

The Project Completion date has been extended from ~~June 30, 2023~~ to **July 31, 2023**.

### CLARIFICATIONS:

C1: Task 1 – Dumping Pits Repair

- a. **No painting is required.**
- b. On the Two (2) West Side Pits, each pit currently has Five (5) braces installed. Add Four (4) braces on each side of the long side of the pit, eight (8) new braces per pit,

total of Sixteen (16) new Horizontal Braces added) to match existing bracing on East Side Pits.

- c. On the two (2) East Side Pits, 'Dog-Leg' Weld or Replace where upper skirting meets lower skirting for a flush surface.

C2: Task 2 – Front Scale Repair

- a. Add Eight (8) Threaded Bolts to hold Access Plates Down
- b. Pipe shall not be in contact with the ground at terminations, so scale can deflect appropriately up & down. Excavate as necessary under end of pipe.

C3: Task 3 – Rail Repairs

- a. Each long side rail section shall have a total of four (4) upright supports on each section. Can utilize existing if needed.

**ADDENDUM ONE ACKNOWLEDGED:**

BY \_\_\_\_\_ TITLE \_\_\_\_\_

(Addendum **must** be signed and returned with bid or receipt of the addendum **must** be acknowledged on the Invitation to Bid



**CITY OF CHEYENNE ITEMIZED BID SHEET FORM**  
**ADDENDUM ONE REVISED**

BID SHEET, BASE BID	
BID PROPOSAL	
PROJECT	Sanitation Division Transfer Station Welding Repairs

Item No.	Description	Unit	Est. Qty	Unit Price (in figures)	Total Price
1	Performance & Payment Bond	LS	1		
2	Mobilization	LS	1		
3	Task 1 – Dumping Pits Repair	LS	1		
4	Task 2 – Front Scale Rail Repair	LS	1		
5	Task 3 – Rail Repairs	LS	1		
6	Force Account	LS	1	\$10,000.00	\$10,000.00

BIDDER: \_\_\_\_\_

TOTAL BID: \_\_\_\_\_